### Diagnostic Instrument Design for the Start up Source & LEBT

Sam K. Mukherjee

This technical note is intended exclusively for internal use inside the SNS Front-End-Systems Group. The primary purpose of the technical note series is to promote rapid dissemination of results for work in progress. No formal review has taken place to ascertain the accuracy of its contents, or the consistency / compatibility of the information with other SNS work.

## Diagnostic Equipment for the startup source and LEBT Sam K. Mukherjee LBNL Mechanical Engineering September 20, 1999

### **Scope**

The R&D test stand for the SNS source #1 has been built on the existing diagnostic spool. The spool contained the horizontal and vertical emittance measuring slits as well as the faraday cup.

The startup source and the LEBT assembly include a new diagnostic spool compatible with the RFQ layout. The diagnostic instruments have to be modified to fit this new spool.

This tech note describes the modifications made on the existing diagnostic equipment.

#### **Description**



Photo shows the Emittance scanner and Faraday cup arrangement.

The new diagnostic spool has 18 inches inside diameter is smaller than the old setup. The individual scanner is modified to match the axial distance by special bracket plate. The face of the scanner shield block is set at 2 cm from the aperture of the last LEBT electrode. The axis alignment is maintained by positioning the scanner mounting flanges within close tolerances in X-Y direction, as well as right angle to each other. The BCD and dimensions of the last electrode plate are copied from the RFQ mounting flange design (Mat Hoff).

The Faraday cup was separated from the Y-axis scanner and mounted on a new manual actuator with 4 inches travel. These three instruments operate through electrical interlocks such that only one can be operated at one time.

This new vacuum vessel is pumped down by an existing CT-8 Cryo-pump and Vat valve setup, mounted on the end plate. An isolation valve (see ME Note M7770) separates the LEBT vacuum vessel and the diagnostic spool.

# **Testing**

The new spool was tested for vacuum leak during LEBT system check. The scanner instrument translator was operated and no interference was noticed.

# **Drawings**

<u> </u>	
21C9926	New Diagnostic Spool
21C9934	End Cover
25B0696	LEBT Vacuum Chamber
25B0726	Bulkhead Plate
21G8986	LEBT Last Electrode









